



Power measurements on the W2E Vertical Axis Water Turbine

MTI-Holland,

Authors:
Ing. R. Stam

Pro-Tide supervisor:
Dr. ir. J. van Berkel
Report version 10-08-2015

Investing in Opportunities



This project has received
European Regional
Development Funding
through INTERREG IV B.



INTERREG IVB





MTI HOLLAND BV



DIV240

Power measurements on the W2E Vertical Axis Water Turbine

**DREDGING
ADVISORY
SERVICES**

**FEASIBILITY
STUDIES**

**RESEARCH AND
DEVELOPMENT**

**MEASURING
AND DIAGNOSTICS**

**MTI Holland BV
P.O. Box 8
2960 AA KINDERDIJK
The Netherlands
Tel. +31 (0)78 6910322
Fax +31 (0)78 6910331**



MTI Holland B.V.

P.O. Box 8, 2960 AA Kinderdijk
6, Smitweg, 2961 AW Kinderdijk

T +31 78 691 03 22
info@mtiholland.com
www.mtiholland.com

**Power measurements on the W2E Vertical Axis Water
Turbine**




Date	Report number	Version	Status	Author
10-8-2015	DIV240	V1.1	Final	R. Stam

Client	Provincie Zeeland / Pro-Tide
Reference number	15008406
Classification	None
MTI order number	71311



Quality control

This report has been reviewed and approved in accordance with the policies of MTI Holland B.V.

	Name	Date	Signature
Composed	R. Stam	10-8-2015	
Reviewed	P.Fremouw	12-8-2015	
Approved	R.A.P. Higler	12-8-2015	

Disclaimer

This document has been prepared by MTI Holland B.V. (MTI) for Provincie Zeeland / Pro-Tide. The opinions and information in this report are entirely those of MTI, based on data and assumptions as reported throughout the text and upon information and data obtained from sources which MTI believes to be reliable.

While MTI has taken all reasonable care to ensure that the facts and opinions expressed in this document are accurate, it makes no guarantee to any person, organization or company, representation or warranty, express or implied as to fairness, accuracy and liability for any loss howsoever, arising directly or indirectly from its use or contents.

This document is dated 10-8-2015



Date
10-8-2015

Reference
DIV240

Version
V1.1

Status
Final

Page
2 of 9

Summary

On the request of Provincie Zeeland / Pro-Tide measurements were taken on the Vertical Axis Water Turbine of Water2Energy B.V. by MTI Holland, dept. Measuring & Diagnostics. Measurements were carried out on June 5- 9, 2015, near the weir complex at Amerongen.

On and around the turbine the following parameters are measured: turbine shaft torque and speed, flow through the turbine and pressure difference over the turbine. The measurements will be analysed in detail by Pro-Tide and the supplier of the turbine, W2E, for this purpose the raw data is provided. However some characteristic plots are already made and presented in this report.



Table of contents

SUMMARY	2
TABLE OF CONTENTS	3
1 INTRODUCTION	4
2 MEASURING APPARATUS AND MEASURING METHODS	5
2.1 TORQUE AND SPEED.....	6
2.2 FLOW	7
2.3 PRESSURE	7
3 RESULTS	8
4 ATTACHMENTS LIST	9
APPENDIX A : CALCULATION OF THE TORQUE SCALE FACTOR	10
APPENDIX B : CALIBRATION CERTIFICATE TRADINCO TRACQ-7 PC	11
APPENDIX C : MEASUREMENT RESULTS: TIME SIGNALS	12
APPENDIX D : MEASUREMENT RESULTS: CHARACTERISTIC PLOTS	16



Date
10-8-2015

Reference
DIV240

Version
V1.1

Status
Final

Page
4 of 9

1 Introduction

On the request of Provincie Zeeland / Pro-Tide measurements were taken on the Vertical Axis Water Turbine of Water2Energy (W2E) B.V. by MTI Holland, dept. Measuring & Diagnostics. Measurements were carried out on June 5- 9, 2015, near the weir complex at Amerongen.

2 Measuring apparatus and measuring methods

On and around the turbine the following parameters are measured: turbine shaft torque and speed, flow through the turbine and pressure difference over the turbine. All signals were logged using a data acquisition device make Dewesoft, type DEWE43, with a sample frequency of 100Hz. A figure of the complete test setup including measuring locations is shown in figure 1.




Figure 1: Complete turbine test setup, measurement locations in red.

2.1 Torque and speed

A view of the turbine shaft as supplied by W2E, with the measurement location, is shown in figure 2. The torque in this shaft ($D_{\text{out-ward}} \varnothing 45\text{mm}$) was measured by means of strain gauges, make HBM, with a resistance of 350 ohm and a k-factor of 2.04. By means of frequency modulated torque meter, fitted on the measured shaft, the strain gauge signals were recorded, through transmitting and receiver equipment make Binsfeld. Calculation of torque in the shaft is based on the shear modulus $G = 8.1939 \cdot 10^{10} \text{N/m}^2$ of the shaft material. The calculation of the torque scale factor can be found in attachment A.

The conditions for an accurate ($\pm 2\%$) torque measurement using strain gauges are:

- Well known shear module of the shaft material
- $> 1.5 \cdot \text{diameter}$ undisturbed shaft length
- $> 30\mu\text{m/m}$ torsional strain

In this case the torsional strain was critical. Only at maximum power the torsional strain meets this criterion: 1620W at 148rpm gives $36\mu\text{m/m}$. Therefore the inaccuracy of torque measurement in general, is more than $\pm 2\%$.

W2E estimated the turbine power to be 3000W at 180rpm, in that case the torsional strain would be $54\mu\text{m/m}$, and therefore meet the criterion for torsional strain over a greater range.

Speed of the shaft was measured through an electronic revolution counter make Banner.




Figure 2: Strain gauges applied on $\varnothing 45\text{mm}$ shaft (left picture), encapsulated strain gauges (centre) and torque and speed measurement location in the test setup (right).

2.2 Flow

Flow in the pipeline (DN1000) feeding the test setup was measured using a clamp on transit time flowmeter, make GE Sensing, type PT878, with a measuring accuracy $\pm 2\%$. The flowmeter was applied on the inlet pipeline, the measurement location is shown in figure 3.



Figure 3: Measurement location transit time flowmeter, located on inlet pipeline.

2.3 Pressure

The pressure difference generated by the turbine was measured using two electronic pressure transducers (make GE Sensing, range -1 to 2 bar and make AE Sensors, range 0 to 1.5bar). Prior to the measurements the sensors were calibrated using a pressure calibrator make Tradinco, type TRAQC-7 PC. A calibration certificate of this device is shown in attachment B. The measuring inaccuracy with these sensors is $\pm 0.5\%$ of full scale, but the measured pressures are much lower than the applied sensor range. Therefore the measurement inaccuracy is estimated to be $\pm 5\%$ of the measured values. Sensors with a more suitable range were not available on the requested short term and not deemed necessary based on the first estimation of the range. The measurement location is shown in figure 4.




Figure 4: Measurement location pressure difference applied by the turbine.

3 Results

Time signals of the measurements are presented in attachments C. The measurements will be analysed in detail by Pro-Tide and the supplier of the turbine, W2E, for this purpose the raw data is provided. The different measurement conditions are tracked by Pro-Tide / W2E, and are displayed in the filenames of the data files.

However some characteristic plots are already made and presented in attachments D. The following signals and calculated results are plot in the attachments:

Measured:

Torque	[Nm]
Speed	[rpm]
Flow	[m/s] (flow velocity in DN1000 pipe)
Pressure1	[kPa]
Pressure2	[kPa]

Calculated:

VolumeFlow	[m ³ /s]	=	Flow * π * pipe_internal_diameter / 4 = Flow * 0.785
PressureDifference	[kPa]	=	Pressure1 – Pressure2
PowerMechanical	[W]	=	Torque * Speed * 2π / 60
PowerHydraulic	[W]	=	VolumeFlow * PressureDifference * 1000 (conversion from kPa to Pa)

The above signals are smoothed with a running average (window of 2 seconds). Hereafter the efficiency is calculated:

Calculated:

$$\text{EfficiencyAfterAveraging [\%]} = (\text{PowerMechanical} / \text{PowerHydraulic}) * 100$$

Note that because of the limitations in measuring accuracy of torque and pressure, the absolute value of the resulting efficiency should be considered as indication only (inaccuracy is estimated to be $\pm 10\%$). However the relative difference in efficiency between different conditions can be considered to be more accurate.



Date
10-8-2015

Reference
DIV240

Version
V1.1

Status
Final

Page
9 of 9

4 Attachments list

- A. Calculation of the torque scale factor
- B. Calibration certificate Tradinco TRAQC-7 PC
- C. Measurement results: time signals
- D. Measurement results: characteristic plots

CALCULATION SCALE FACTOR TORQUE MEASUREMENT



Ship: W2E turbine
 Shaft: turbine shaft

Input

Shaft data

Power P 1.62 [kW]
 Speed n 148 [rpm]
 Diameter outward D_o 0.045 [m]
 Diameter inward D_i 0.000 [m]
 Shear module* G 8.1939 [10^{10} N/m²]

Strain gage data

Resistance R_{stg} 0.35 [k Ω]
 K-factor k 2.04 [-]

* [for pump measurement, default G = 8.1939 * [10^{10} N/m²], actual shear module is included in pump measurement sheet]

Calculation settings

Starting torque $f_{M,start}$ 1 * M_{nom}

Measurement system settings

Resistance calibration R** R_c 437.4 [k Ω]
 Scaleparts calibration SP_c 7980 [SP]

** [Binsfeld: ref1 = 437.4 k Ω]

Calculation

Shaft torque / strain

Speed ω 15.499 [rad/s]
 Maximum torque M_{max} 0.1045 [kNm]
 Polair moment of inertia I_p 0.00000 [m³]
 Maximum strain ϵ_{max} 35.64812 [μ m/m]

Strain gage calibration

Sensitivity at cal. V_c 199.8858 [μ V/V]
 Simulated strain at cal. ϵ_c 98.0616 [μ m/m]
 Simulated torque at cal. M_c 0.2875 [kNm]

Scale factor f 3.6E-05 [kNm/SP]
 0.036032 [Nm/SP]
 10V= 360.3166 [Nm]

T.C.L. Tradinco Calibration Laboratory

CALIBRATION CERTIFICATE

Page 1 of 2

Certificate number : 21500587B

Applicant MTI Holland B.V.
Smitweg 6
2961 AW Kinderdijk

Instrument Digital pressure calibrator
Manufacturer Tradinco Instruments
Type TRAQC-7 PC
Serial number 14.06.117/11653
Service number 17468
Customer identification number -

Calibration method This calibration is carried out with :
Deadweight tester type : T2300/1 S/N : 6612/91 Cal. Due : 18 July 2018

During calibration a testpressure is put under a calibrated measuring piston which is loaded with calibrated weights

Environmental conditions Temperature: 20.0°C ± 2°C
Humidity: 55 %rh ± 25 %rh

Date / period of calibration 20 April 2015

Results See following page(s)

Uncertainty ± 0.012 % of full scale with use of correction figures in the range of (0 ÷ 10) bar


The reported uncertainty is based on a standard uncertainty multiplied by a coverage factor of $k = 2$, which provides a confidence level of approximately 95 %.
The standard uncertainty has been determined in accordance with document EA-4/02.

Calculated by software revision: 2.7.6.6/2.33

Traceability The measurements have been executed using standards for which the traceability to (inter)national standards has been demonstrated towards the RvA.

Date 20 April 2015

Name S. Baidjnath-Misier
Head of TCL



T.C.L. Tradinco Calibration Laboratory

CALIBRATION CERTIFICATE

Page 2 of 2

Certificate number : 21500587B

	Standard	Instrument
Service number		17468
Type	T2300/1	TRAQC-7 PC
Manufacturer	Tradinco Instruments	Tradinco Instruments
Description	Deadweight tester	Digital pressure calibrator
Serial number	6612/91	14.06.117/11653
Range	(0.2 ÷ 35) bar	(-1 ÷ 10) bar
Medium	Air	Air
Accuracy	±0.01 % R	±0.02 % FS full scale = 10 bar
Temperature	20.0°C ± 0.5°C	

MP.	STANDARD		INSTRUMENT					
	INPUT UP bar	INPUT DOWN bar	READING UP bar	READING DOWN bar	ERROR UP % FS	ERROR DOWN % FS	LIMIT UP % FS	LIMIT DOWN % FS
1	0.00000	0.00000	0.0000	0.0003	0.000	0.003	± 0.020	± 0.020
2	1.00001	1.00001	0.9998	0.9994	-0.002	-0.006	± 0.020	± 0.020
3	2.00006	2.00006	1.9998	1.9994	-0.003	-0.007	± 0.020	± 0.020
4	3.00015	3.00015	2.9998	2.9995	-0.004	-0.007	± 0.020	± 0.020
5	4.00022	4.00022	4.0001	3.9995	-0.001	-0.007	± 0.020	± 0.020
6	5.00026	5.00026	5.0001	4.9996	-0.002	-0.007	± 0.020	± 0.020
7	6.00040	6.00040	6.0002	5.9999	-0.002	-0.005	± 0.020	± 0.020
8	7.00045	7.00045	7.0005	7.0001	0.000	-0.004	± 0.020	± 0.020
9	8.00059	8.00059	8.0006	8.0003	0.000	-0.003	± 0.020	± 0.020
10	9.00066	9.00066	9.0012	9.0010	0.005	0.003	± 0.020	± 0.020
11	10.0007		10.0013		0.006		± 0.020	

This range has not been adjusted (As found is as left calibration).

Customer ID. no. :-
 Customer ref. : 602510
 Our ref. : 61500826
 Customer : MTI Holland B.V.

Calibrated by
 TCL Technician

P. Verhoef
 Cal. date : 20 April 2015

Approved by
 Head of TCL

 S. Bardjani-Misier
 Date : 20 April 2015
 Berkel en Rodenrijs



Date
10-8-2015


Reference
DIV240

Version
V1.1

Status
Final

Attachments

Appendix C : Measurement results: time signals





Date
10-8-2015


Reference
DIV240

Version
V1.1

Status
Final

Attachments

Datafile: W2E_ProTide_CurveB_33,37,42Hz_2015_06_08_110116.d7d





Date
10-8-2015


Reference
DIV240

Version
V1.1

Status
Final

Attachments

Datafile: W2E_ProTide_CurveC_33,37,42Hz_2015_06_08_154230.d7d





Date
10-8-2015


Reference
DIV240

Version
V1.1

Status
Final

Attachments


Datafile: W2E_ProTide_CurveD_33,37,42Hz_2015_06_09_093244.d7d






Appendix D : Measurement results: characteristic plots

Datafile: W2E_ProTide_CurveA_42,37,33Hz_2015_06_08_135122.d7d




VolumeFlow: - [m3/s]	ACT
0.63	
Speed: - [rpm]	ACT
75.3	
PressureDifference/AVE: - [kPa]	
17	
PowerMechanical/AVE: - [W]	ACT
318	
PowerHydraulic/AVE: - [W]	ACT
1075	
EfficiencyAfterAveraging: - [%]	
30	

Datafile: W2E_ProTide_CurveA_42,37,33Hz_2015_06_08_135122.d7d



VolumeFlow: - [m3/s]	ACT
0.75	
Speed: - [rpm]	ACT
96.6	
PressureDifference/AVE: - [kPa]	
22	
PowerMechanical/AVE: - [W]	ACT
673	
PowerHydraulic/AVE: - [W]	ACT
1702	
EfficiencyAfterAveraging: - [%]	
40	

Datafile: W2E_ProTide_CurveA_42,37,33Hz_2015_06_08_135122.d7d



VolumeFlow: - [m3/s]	ACT
0.94	
Speed: - [rpm]	ACT
133.0	
PressureDifference/AVE: - [kPa]	
32	
PowerMechanical/AVE: - [W]	ACT
1444	
PowerHydraulic/AVE: - [W]	ACT
3028	
EfficiencyAfterAveraging: - [%]	
48	



Date
10-8-2015


Reference
DIV240

Version
V1.1

Status
Final


Attachments

Datafile: W2E_ProTide_CurveB_33,37,42Hz_2015_06_08_110116.d7d




VolumeFlow; - [m3/s]	ACT	0.62
Speed; - [rpm]	ACT	106.2
PressureDifference/AVE; - [kPa]		2.2
PowerMechanical/AVE; - [W]	ACT	623
PowerHydraulic/AVE; - [W]	ACT	136.1
EfficiencyAfterAveraging; - [%]	A	46

Datafile: W2E_ProTide_CurveB_33,37,42Hz_2015_06_08_110116.d7d



VolumeFlow; - [m3/s]	ACT	0.74
Speed; - [rpm]	ACT	123.1
PressureDifference/AVE; - [kPa]		3.0
PowerMechanical/AVE; - [W]	ACT	987
PowerHydraulic/AVE; - [W]	ACT	219.2
EfficiencyAfterAveraging; - [%]	A	45


Datafile: W2E_ProTide_CurveB_33,37,42Hz_2015_06_08_110116.d7d



VolumeFlow; - [m3/s]	ACT	0.94
Speed; - [rpm]	ACT	148.9
PressureDifference/AVE; - [kPa]		4.3
PowerMechanical/AVE; - [W]	ACT	1619
PowerHydraulic/AVE; - [W]	ACT	402.4
EfficiencyAfterAveraging; - [%]	A	40




Datfile: W2E_ProTide_CurveC_33,37,42Hz_2015_06_08_154230.d7d




VolumeFlow; - [m3/s]	ACT	0.60
Speed; - [rpm]	ACT	14.15
PressureDifference/AVE; - [kPa]		4.2
PowerMechanical/AVE; - [W]	ACT	650
PowerHydraulic/AVE; - [W]	ACT	2486
EfficiencyAfterAveraging; - [%]	A	26

Datfile: W2E_ProTide_CurveC_33,37,42Hz_2015_06_08_154230.d7d



VolumeFlow; - [m3/s]	ACT	0.69
Speed; - [rpm]	ACT	17.74
PressureDifference/AVE; - [kPa]		5.1
PowerMechanical/AVE; - [W]	ACT	596
PowerHydraulic/AVE; - [W]	ACT	3581
EfficiencyAfterAveraging; - [%]	A	17

Datfile: W2E_ProTide_CurveC_33,37,42Hz_2015_06_08_154230.d7d



VolumeFlow; - [m3/s]	ACT	0.91
Speed; - [rpm]	ACT	65.2
PressureDifference/AVE; - [kPa]		4.9
PowerMechanical/AVE; - [W]	ACT	296
PowerHydraulic/AVE; - [W]	ACT	4480
EfficiencyAfterAveraging; - [%]	A	7

N.B.: Note different Power scaling in vertical axis in last graph.